

<b>IT Parking Lot - M.P. Vaughn Construction</b>	<b>Total</b>
IT Parking Lot	\$49,600.00
<b>IT Parking Lot Total- M.P. Vaughn Construction</b>	<b>\$49,600.00</b>

<b>IT Parking Lot - Work Description</b>	<b>Quantity</b>	<b>J.P. Vaugh Construction</b>	<b>M.P. Vaughn Construction</b>	<b>Kemery Contracting</b>	<b>Kemery Contracting Subtotal</b>	<b>Frizzell's Service</b>	<b>Frizzell's Service Subtotal</b>
Turnkey for the following 65'x65' parking with 25' wide approach	1	\$49,600.00	\$49,600.00	\$7,798.00	\$57,500.00	\$54,154.00	\$54,154.00
Excavate 12" of dirt and haul off (haul to on site location)		\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00
Prep and place for 6" of 3500 PSI concrete paving with curb on perimeter							
Reinforced with #4 rebar @ 24" each way							
Sawcut control joints @ 10' each way							
Joints seal all control joints							
Striping for 14 parking spaces							
Backfill behind curb on all sides and finish grade							
<b>Total</b>			<b>\$49,600.00</b>		<b>\$57,500.00</b>		<b>\$54,154.00</b>