

HORTICULTURE

Qty

SOLE SOURCE

**AMERICAN PLANT PRODUCTS
AND SERVICES, INC.**

HORTICULTURE

30'X96' Pad Wall Renovation -	\$10,797.44
1 Materials - List Attached	
Labor to rebuild endwall framing & rack and pinion pad vent complete with new corrugated polycarbonate glazing	\$4,800.00
Labor to rebuild Kool Cel pad System and pad plumbing	\$2,500.00
Sub Total	\$18,097.44
Shipping	Incl
TOTAL	\$18,097.44

AMERICAN PLANT PRODUCTS AND SERVICES, INC.

9200 N.W. 10th Oklahoma City, OK 73127

(405) 787-4833 Toll Free 1-800-522-3376 Fax: (405)789-2352

www.americanplant.com

E-mail: appas@americanplant.com

Kara Murphy
Mid-America Technology Center
27438 State Highway 59
Wayne, OK 73095
405.659.3427
kmurphy@matech.edu

March 31, 2021

Re: Quote: 30' x 96' Pad Wall Renovation

Kara,

We are pleased to provide a renovation quote for you to review. The Quote includes all greenhouse materials and accessories listed including labor. Please contact us if you have any questions about the renovation. After your review, please call me if you have any questions or when you are ready to place your order.

We also offer benches, fertilizer injectors, growing materials and most any other equipment that is required to maintain high quality plants in your greenhouse environment. We can supply pots, potting soil, chemicals, sprayers, soil sterilizers, thermometers, and any other supplies that you may need for your growing operation.

Note: Price excludes any applicable sales tax, if you are tax exempt please send in your card when ordering.

Your friends in Horticulture!

Alex Moore
Horticulture Sales
(405) 787-4833

Rodd Moesel
President
(405) 787-4833

Dave Grammer
Construction Manager
(405) 919-4496

Pad Wall Renovation - Mid-America Technology Center

Quantity	GREENHOUSE MATERIALS	Unit Price	Extended Price
6	24' x 2" x 2" Galvanized square tubing #50-242	\$ 126.68	\$ 760.08
40	Nexus 2 hole lugs #51-02	\$ 2.38	\$ 95.20
3	2" x 6" x 1/2" Steel plates	\$ 24.00	\$ 72.00
3	2" x 2" x 8' Galvanized steel square tubing	\$ 94.00	\$ 282.00
1	Plate welding & cold galvanizing	\$ 150.00	\$ 150.00
6	3/8" x 5" Stainless steel anchor bolts with nuts and washers	\$ 2.50	\$ 15.00
1	29' x 4' Kool cel distribution and return system PDR4 stainless steel	\$ 2,284.26	\$ 2,284.26
29	4" x 12" x 48" Kool cel pads #55-41248	\$ 23.97	\$ 695.13
2	2" x 4" x 24' Galvanized square tubing #50-2024	\$ 261.06	\$ 522.12
6	1 3/4" x 1 3/4" x 6" Purlin splice #50-114	\$ 7.50	\$ 45.00
1	Cold galvanizing compound #46-50180	\$ 14.48	\$ 14.48
4	#12 x 1" Self drilling tek screws w/o washers #53-512100	\$ 13.05	\$ 52.20
1	Set of aluminum flashing 30' x 6" x 1/16"	\$ 255.00	\$ 255.00
4	NPI urethane limestone caulk #46-0013	\$ 7.68	\$ 30.72
6	49.6" x 16'4" Clear Corrugated Polycarbonate	\$ 100.43	\$ 602.58
2	49.6" x 20' Clear Corrugated Polycarbonate	\$ 120.30	\$ 240.60
4	Lap Fasteners	\$ 9.00	\$ 36.00
1	#9 x 1" Woodgrip Screw for joining corrugated panels	\$ 13.37	\$ 13.37
2	SD Tek w/w #12 x 1 1/2"	\$ 22.80	\$ 45.60
60	3' Boxrib corrugated sealing foam	\$ 1.56	\$ 93.60
1	30' Endwall Rack and pinion Pad Vent	\$ 2,912.50	\$ 2,912.50
1	VC100 Wadsworth Vent Motor	\$ 1,260.00	\$ 1,260.00
1	Wadsworth LST Vent Control Panel	\$ 320.00	\$ 320.00
Greenhouse Materials Total			\$ 10,797.44

Quantity	LABOR	Unit Price	Extended Price
1	Labor to rebuild endwall framing and rack and pinion pad vent complete with new corrugated polycarbonate Glazing	\$4,800.00	\$4,800.00
1	Labor to rebuild Kool Cel pad System and pad plumbing.	\$2,500.00	\$2,500.00
Labor Total			\$7,300.00

GREENHOUSE TOTAL			\$ 18,097.44
-------------------------	--	--	---------------------

Labor Excludes any electrical, gas or plumbing work except kool-cel components.